

THERMOPLASTIC AND RETROREFLECTIVE PAVEMENT MARKINGS			
ROAD NAME	TYPE 'I' REFLECTORS	THERMOPLASTIC STRIPE (YELLOW)	THERMOPLASTIC STRIPE (WHITE) (L/F)
FRONTAGE ROAD	115	2650	0
ENTLER AVE	36	724	0
SPEEDWAY AVE	0	0	0
TOTALS	152	3,374	0

NOTES:  
STRIPING QUANTITIES ARE MEASURED IN LENGTHS OF EQUIVALENT 4' WIDTH.

**SIGNAGE SCHEDULE**


QUANTITY	SIGN PANELS	POST SIZE/TYPE	INSTALLATION LOCATION	SIGN MESSAGE
2	C-1B	4" X 4" / WOOD	POST INSTALLATION	ROAD CONSTRUCTION AHEAD
2	C-13	4" X 4" / WOOD	POST INSTALLATION	END CONSTRUCTION
1	R1-1	2' X 3' / TELEPAR	POST INSTALLATION	STOP
1	CHEVRONS	6" X 6" / WOOD(8TD 8-3D)	GUARD PANEL	NONE

FOR ROADWAY THERMOPLASTIC AND RETROREFLECTIVE MARKINGS SEE ESTIMATED QUANTITIES THIS SHEET.

PLACE A-C-13 (ROAD CONSTRUCTION AHEAD) SIGN AND A-C-15 (END CONSTRUCTION) SIGN APPROX. 500' FROM THE PROJECT LIMITS OR AS DETERMINED BY THE ENGINEER. (SEE SHEETS 4-9 FOR PROJECT LIMITS)

**PLANS FOR THE CONSTRUCTION OF S.R. 99 FRONTAGE ROAD FROM ENTLER AVENUE TO COMANCHE CREEK STRIPING & SIGNAGE PLAN SHEET**

PLOT DATE: 7/23/09



10  
502553-05-1  
1