

TRAFFIC STRIPING AND PAVEMENT MARKER QUANTITY LIST

*** STRIPING QUANTITIES - LINEAR FEET**

ROAD NAME	DETAIL 12	DETAIL 25	DETAIL 27B	DETAIL 38
SKYWAY TOTALS	19,114	19,114	19,114	500

*** PAVEMENT MARKER QUANTITIES**

SKYWAY	TYPE C	TYPE G	TYPE H	THERMOPLASTIC (YELLOW) (LF)	THERMOPLASTIC (WHITE) (LF)
TOTALS	399	22	399	19,114	39,228

*** For estimating purposes only, exact quantities shall be as determined by the Engineer**

Note: Detail 38 measured and paid for as two 4-inch stripes per LF shown

THERMOPLASTIC PAVEMENT MARKING DETAILS **

S.F. shown are for estimating purposes only. Exact quantities shall be as determined by the Engineer.

- | | |
|------------------------------|-------------------------------------|
| 1. "STOP" | 3 EACH @ 22 S.F. = 66 S.F. |
| 2. Stop Bar @ 46 S.F. | 46 S.F. = 46 S.F. |
| 3. TYPE II ARROW | 2 EACH @ 45 S.F. = 90 S.F. |
| 4. TYPE III ARROW | 2 EACH @ 42 S.F. = 84 S.F. |
| 5. TYPE V ARROW | 14 EACH @ 33 S.F. = 462 S.F. |
| 6. TYPE VI ARROW | 2 EACH @ 42 S.F. = 84 S.F. |

PROJECT TOTAL = SAY 1,200 S.F.

**** Square footage based on diagrams shown in State of California Dept. of Transportation's
May 2006 Standard Plans**

COUNTY OF BUTTE, DEPARTMENT OF PUBLIC WORKS

Plans for Overlay of the Skyway Chico-Bound Lanes

From 3.12± to 6.74± miles west of Skyway Crossroad

County Project No. 51261-07-1

Project Length = 3.62± Miles